

Name of work:- Renovation of Prof. S.P. Chourasia office in Chemical Engineering Departmentat MNIT Campus Jaipur.

G-Schedule

| S.No | Qty | Items | Unit | Rate | Amount |
|------|-------|---|------|---------|----------|
| 1 | | P & F 1st quality Heavy Duty Vitrified Double Charged tiles on floor, skirting and steps etc.in different sizes (thickness minimum 10mm) with water absorption less than or equal 0.08% and conforming to IS 15622 of approved make in all colour and shade, laid with 20 mm thick CM 1: 4 including grouting the joints with white cement and matching pigment etc complete. | | | |
| A | 24.69 | size 800 mm X 800mm | Sqm | 1178.00 | 29084.82 |
| 2 | | Providing and fixing tiled false ceiling of approved materials of size 595X595 mm in true horizontal level suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams per sqm both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24X38 mm made from 0.30 mm thick (minimum) sheet spaced at 1200 mm center to center and cross "T" of size 24X25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200X600 mm and secondary cross "T" of length 600 mm and size 24X25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200X600 mm panel to form grids of 600X600 mm and wall angle of size 24X24X0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/ making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 X 37 X 25 X 1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanized butterfly level clips of size 85 X 30 X 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in- | | | |
| A | 22.73 | GI Metal Ceiling Lay in perforated Tegular edge global white | Sqm | 1536.00 | 34913.28 |
| 3 | | Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade including all scaffolding: | | | |
| | | Old work (one or more coats) including scrapping | | | |
| A | 72.37 | Colour Change | Sqm | 14.00 | 1013.18 |

| | | | | | |
|---|-------|---|-----|-------|----------|
| 4 | 72.37 | Removing dry or oil bound distemper by scrapping sand papering and preparing surface smooth including necessary repairs to scratches by sandla/loi and all scaffolding (for colour changing only) | Sqm | 3.90 | 282.24 |
| 5 | | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : | | | |
| A | 40.00 | One or more coats on old work. | Sqm | 31.00 | 1240 |
| | | TOTAL | | | 66533.52 |
| | | | | | RS |

EXECUTIVE ENGINEER
ESTATE SECTION MNIT
JAIPUR

I/We hereby agree to execute the work @%Above/Below of Schedule 'G'

SIGNATURE OF THE CONTRACTOR WITH FULL POSTAL ADDRESS