

Name of work:- Repairing work of roof at Various Hostels at MNIT Campus Jaipur.

G-Schedule

S.No	Qty	Items	Unit	Rate	Amount
1	660	Repair to damaged RCC slabs, beams and columns etc for strengtheing with cement mortar 1 : 2 in following steps i) Choping losse and cracked concrete to required depth, cleaning the exposed surface of steel and concrete with wire brush and sand papering , cleaning of concrete surface with water as necessary and getting dried. ii) Applying Epoxy primer on the exposed steel bars. iii) Applying Epoxy hardener and resin mix (as per manufactured's specification) on concrete and steel bars with brush. iv)Speading dry cement mortar 1 : 2 mix over epoxy treated wet surface and allow it to dry for one day. v) Plastering the surface with cement sand mortar 1 : 3 upto depth of 30mm complete. vi) Cure the plastered surface for 15 days All work including scaffolding etc. complete in all respect.	Sqm	1425.00	940500.00
			Total		940500.00

Grand total

Rs.

**EXECUTIVE ENGINEER
ESTATE SECTION MNIT
JAIPUR**

I/We hereby agree to execute the work @.....%Above/Below of Schedule 'G'

SIGNATURE OF THE CONTRACTOR WITH FULL POSTAL ADDRESS